

Click To Edit Master Title Style

sCO₂ Development at Southwest Research Institute

Stefan D. Cich

Southwest Research Institute

- Founded in 1947, 2500 employees
- Machinery Department
 - Mechanical Engineering Division Focus on applied engineering research and development
 - Design, Fabrication, and Testing
- Specialties
 - Turbomachinery design and testing
 - Root cause failure analysis
 - Rotordynamic design/audit
 - Pipeline/plant simulation
 - CFD and FEA analysis
 - Test stand design
 - Performance testing
 - Thermodynamic cycles analysis
- Active DOE Programs in
 - Power Generation
 - Energy Storage
 - Renewable Energy
 - Improved Fossil Energy



Supercritical CO2 Cycle Applications

Primary Power

- High grade heat
- Optimized for system efficiency
- 0.3-2000 MWe



Concentrating
Solar Power




Fossil Fuel




Nuclear

Bottoming Cycles

- Low grade heat
- Optimized for net power
- 2-10 MWe




Waste Heat
Recovery




Geothermal


Simple sCO₂ Recuperated Cycle




Recompression sCO₂ Cycle




Transformation sCO₂ cycle defines a new curve



How it works – thermodynamic benefit




sCO₂ Power Gen Application Space



Smaller Turbomachinery

20 MW Steam Turbine



15 MW sCO₂ Turbine


- 150 lb rotor, 7" dia, 27,000 RPM



SwRI sCO₂ Technology Focus Areas


System and Cycles

- Design and evaluation for primary power and waste heat recovery
- Oxy-combustion component and system design and test
- System optimization with machinery design and component selection




Turbines

- Component development and demonstration – Bearings, Seals
- Radial and axial flowpath machines
- Machinery design and rotordynamics




Compressors

- Flowpath design and simulation
- Machinery design and rotordynamics
- Machinery performance testing






Heat Exchangers

- Design and optimization for cost, performance, and manufacturing
- Simulation including CFD, FEA, and CHT



Progressing to Pilot Scale Demonstration

Individual Cycle and Component Development



Leveraging \$60 million in DOE investments into sCO₂ technology development

Integrated Pilot Scale System Demonstration



- Demonstrate sCO₂ system operability
- Verify component performance
- Show the potential for lower cost of electricity and high thermodynamic efficiency

Supercritical Transformational Electric Power (STEP) Program

Scope: Design, construct, commission, and operate a 10 MWe sCO₂ Pilot Plant Test Facility


Goal: Advance state of the art for high temperature sCO₂ power cycle performance from Proof of Concept (TRL3) to System Prototype validated in an operational system (TRL7)

Team: Gas Technology Institute (GTI)
Southwest Research Institute[®] (SwRI[®])
General Electric Global Research (GE-GR)
U.S. Department of Energy (NETL)

Schedule: Three budget phases over six years (2016-2022)

Cost: \$119MM Total / \$84MM Federal Funding

Building a flexible platform for long-term use to validate component performance, quantify cycle efficiency, and study plant operability in an integrated, grid-connected system.



Supercritical Transformational Electric Power (STEP) Program


Demonstrate pathway to RCBC cycle efficiency > 50%

Demonstrate cycle operability up to 700°C turbine inlet temperature and 10 MWe net power generation

Quantify performance benefits:


- 2-5% point net plant efficiency improvement
- 3-4% reduction in LCOE
- Reduced emissions, fuel, and water usage

Reconfigurable facility to accommodate future testing



STEP Test Facility



- Facility design
 - Provides sufficient flexibility to support future testing and demonstration activities
- Key facility features
 - Process hardware located in a controlled highbay
 - Oversized machinery foundations
 - Natural gas fired heat source
 - Provisions for auxiliary cooling capacity
 - 16 MWe distribution capacity, 10 MWe interconnect
- Ground Breaking October 15, 2018





GE-Apollo High-Efficiency sCO₂ Centrifugal Compressor Development (GE, SwRI for DOE EERE)

- Develop high-efficiency sCO₂ compression system for operation near the critical point
 - Main Compressor Efficiency of 80% using a high efficiency centrifugal impeller
 - Variable IGV/OGV to accommodate fixed speed operation
 - Extended flow range to accommodate swings in ambient temperature
- Aerodynamic design provided by GE and implemented into a compressor design provided by SwRI
- Full scale testing at 10 MWe sCO₂ cycle conditions to verify compressor mechanical and aerodynamic performance over a range of operating conditions

Compressor Mechanical Design



Compressor Aerodynamic Design




Flowpath Simulation




Variable IGV Design

Apollo: Ultra High Efficiency Integrally-Gearred sCO₂ Compressor (SwRI, Hanwha for DOE EERE)


- Design a sCO₂ integrally geared compander (IGC)
 - Combining compression and expansion stages into a single integrally geared housing connected to a low speed motor/generator.
- Benefits:
 - Reduced footprint
 - Potential cost reduction up to 35%
 - Utilizes a low speed commercially available driver/generator
 - Modular (Small Industrial [5MW] to Small Utility [50 MW])
 - High efficiency over a wide range of operating conditions
 - Improved cycle controllability



Typical IGC Package





Conventional Turbomachinery Train



Testing of Shaft End Seals for Utility Scale sCO₂ Turbines (GE, SwRI for DOE NETL)

- Seals for utility scale (450 MWe) sCO₂ turbines are not commercially available
 - 24 in. end seals at 75 bar
- Film-riding face seals increase cycle efficiency by 0.6-0.8 points
- GE is developing large diameter face seal technology
- SwRI developing rig to test full-scale seal prototype with sCO₂
- Leverages existing test hardware developed for EERE SunShot



sCO₂ Program Status

- Sunshot Turbine – Complete
 - Achieved design temperature, speed, and pressure
 - Obtained valuable performance, design and control system data for future development
- Apollo Compressor – Middle of Testing
 - Achieved design speed and pressure. Compressor CO₂ near the dome
 - Currently troubleshooting mechanical issues and will continue testing in 2020
- Apollo Comander - Assembly
 - All major components have been delivered
 - Will be testing compressor followed by full power loop
- Utility Scale Seals Test Rig – Middle of Testing
 - Initial mechanical assembly and mechanical test complete
 - Will assembled with face seals and run full pressure performance tests
- STEP Pilot Scale Plant – Construction and Procurement
 - Design complete. Building is being constructed
 - Testing will begin in late 2020
- Oxy Combustion – Beginning
 - Received funding for one combustor test
 - Currently have proposals for more to develop oxy combustion technologies and further advance turbine development